

土工事数量集計書

株式会社 XXX x X

工事名 : demoKS2 + 杭

集計区分	根切	地業				埋設体積												
		碎石地業	床付け	捨てコン	型枠													
独立基礎	428.891	8.002	80.02	4.001	155.4	70.695												
基礎柱						6.309												
地中梁	61.255	2.583	25.831	1.292	126.505	30.462												
スラブ																		
土間																		
腰壁																		
布基礎																		
合計	490.146	10.585	105.851	5.293	281.905	107.466												
<table style="width: 100%; border: none;"> <tr> <td style="width: 15%;">不要土</td> <td style="width: 15%; text-align: right;">107.466 m³</td> <td style="width: 15%;">(=埋設体積)</td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> <td style="width: 15%;"></td> </tr> <tr> <td>埋戻し</td> <td style="text-align: right;">382.68 m³</td> <td>(=根切 - 埋設体積)</td> <td style="text-align: right;">382.68 =</td> <td style="text-align: right;">490.146 -</td> <td style="text-align: right;">107.466</td> </tr> </table>							不要土	107.466 m ³	(=埋設体積)				埋戻し	382.68 m ³	(=根切 - 埋設体積)	382.68 =	490.146 -	107.466
不要土	107.466 m ³	(=埋設体積)																
埋戻し	382.68 m ³	(=根切 - 埋設体積)	382.68 =	490.146 -	107.466													